

# National Register of Historic Places Registration Form

This form is for use in nominating or requesting determinations of eligibility for individual properties or districts. See instructions in *Guidelines for Completing National Register Forms* (National Register Bulletin 16). Complete each item by marking "x" in the appropriate box or by entering the requested information. If an item does not apply to the property being documented, enter "N/A" for "not applicable." For functions, styles, materials, and areas of significance, enter only the categories and subcategories listed in the instructions. For additional space use continuation sheets (Form 10-900a). Type all entries.

### 1. Name of Property

historic name DeJean House  
other names/site number \_\_\_\_\_

### 2. Location

street & number 3603 Frederic Street N/A not for publication  
city, town Pascagoula N/A vicinity  
state Mississippi code MS county Jackson code 59 zip code 39567

### 3. Classification

Ownership of Property <input checked="" type="checkbox"/> private <input type="checkbox"/> public-local <input type="checkbox"/> public-State <input type="checkbox"/> public-Federal	Category of Property <input checked="" type="checkbox"/> building(s) <input type="checkbox"/> district <input type="checkbox"/> site <input type="checkbox"/> structure <input type="checkbox"/> object	Number of Resources within Property <table border="0"> <tr> <td style="text-align: center;">Contributing</td> <td style="text-align: center;">Noncontributing</td> </tr> <tr> <td style="text-align: center;">_____</td> <td style="text-align: center;">_____</td> </tr> <tr> <td style="text-align: center;">2</td> <td style="text-align: center;">_____</td> </tr> <tr> <td style="text-align: center;">_____</td> <td style="text-align: center;">buildings</td> </tr> <tr> <td style="text-align: center;">_____</td> <td style="text-align: center;">sites</td> </tr> <tr> <td style="text-align: center;">_____</td> <td style="text-align: center;">structures</td> </tr> <tr> <td style="text-align: center;">_____</td> <td style="text-align: center;">objects</td> </tr> <tr> <td style="text-align: center;">2</td> <td style="text-align: center;">0</td> </tr> <tr> <td style="text-align: center;">_____</td> <td style="text-align: center;">Total</td> </tr> </table>	Contributing	Noncontributing	_____	_____	2	_____	_____	buildings	_____	sites	_____	structures	_____	objects	2	0	_____	Total
Contributing	Noncontributing																			
_____	_____																			
2	_____																			
_____	buildings																			
_____	sites																			
_____	structures																			
_____	objects																			
2	0																			
_____	Total																			

Name of related multiple property listing:  
Historic Resources of Pascagoula, MS

Number of contributing resources previously listed in the National Register 0

### 4. State/Federal Agency Certification

As the designated authority under the National Historic Preservation Act of 1966, as amended, I hereby certify that this  nomination  request for determination of eligibility meets the documentation standards for registering properties in the National Register of Historic Places and meets the procedural and professional requirements set forth in 36 CFR Part 60. In my opinion, the property  meets  does not meet the National Register criteria.  See continuation sheet.

Kenneth H. P. Paul Jan. 22, 1993  
Signature of certifying official Date  
Deputy State Historic Preservation Officer  
State or Federal agency and bureau

In my opinion, the property  meets  does not meet the National Register criteria.  See continuation sheet.

\_\_\_\_\_  
Signature of commenting or other official Date  
\_\_\_\_\_  
State or Federal agency and bureau

### 5. National Park Service Certification

I, hereby, certify that this property is:

entered in the National Register.  
 See continuation sheet.

determined eligible for the National Register.  See continuation sheet.

determined not eligible for the National Register.

removed from the National Register.

other, (explain:)

Signature of the Keeper

Date of Action

**6. Function or Use**

Historic Functions (enter categories from instructions)

Domestic/Single Dwelling

Current Functions (enter categories from instructions)

Domestic/Single Dwelling**7. Description**

Architectural Classification

(enter categories from instructions)

Queen Anne

Materials (enter categories from instructions)

foundation Concretewalls AsbestosShingleroof Asbestos

other \_\_\_\_\_

Describe present and historic physical appearance.

Facing east onto North Frederic Street, the DeJean House is adjacent to a commercial/industrial area of Pascagoula. Designed and built in 1906 by Ambrose Linder for Valsin Pierre DeJean, the house is a Queen Anne cottage that has many features typical of this architectural style. The property is bordered on two sides by the original cast iron fence with wrought iron details, manufactured by the Stewart Iron Works of Cincinnati, Ohio. The fence has been maintained in excellent condition and is a distinct feature from the street. To the south side of the house is an alley that serves this and adjacent properties.

The DeJean House is a one-and-one-half story, wood frame structure with a one-story asymmetrical wraparound front porch extending the full width of the residence and turning at a circular pavilion on the south corner to run the full length of the south elevation. The hipped porch roof is supported by full-height turned columns with decorative lace-like jigsaw brackets. Spanning from column to column is a spindled balustrade with plain hand and foot rails. On the main facade, the north end of the porch was enclosed in 1912 when a physician recommended an open air atmosphere for the treatment of DeJean's son, who was diagnosed with rickets. Since this construction occurred shortly after the house was built, the exterior and interior finishes of the sun porch are similar to those of the house. From the interior, the feeling and details remain as an enclosed porch. The one-over-one, double-hung windows of leaded glass with diamond-shaped mullions are more detailed and ornate than any other windows in the house. This amount of detail allows the enclosure to be more than functional; it adds some character, and along with the extended roof structure helps express this construction as a change to the original.

Intersecting north-south and east-west gables comprise the primary roof structure with a secondary gable on the south elevation and a pedimented gable at the hipped porch roof above the front east entry. The dominant gable on the east (front) elevation is centered over a bay window. This gable is faced with patterned wood shingles and has a round-arched window opening. Roof shingles on the house are asbestos tiles laid in a diamond pattern with clay tiles for hip and ridge tiles. The roofing of the sun porch is constructed of exposed rafters with diagonal supports and is hipped

United States Department of the Interior  
National Park Service

**National Register of Historic Places  
Continuation Sheet**

DeJean House, Pascagoula, Jackson County, Mississippi

Section number 7 Page 1

---

at the northeast corner. Due to a fire across the street at a laundry which damaged (scorched) the original wood lap siding along the front of the house, the asbestos siding was added over the original siding in 1954.

The main entry to the house is a single-leaf glazed and panelled door topped by a single-light etched glass transom. All of the windows of the house, except the windows to the kitchen and laundry room, are original. The windows to the parlor and dining room are floor-length, one-over-two, double-hung sash. These windows are protected by full-height, louvered shutters secured with original brass hardware. The exterior trim is simple with a decorative crown.

The interior of the house has a central hallway, with the parlor, dining room and kitchen to the south and the enclosed sun porch, two bedrooms and a bathroom to the north. The west end of the hall originally opened onto a rear porch, but this porch was enclosed in 1954 to create a laundry room. An elaborately detailed spindlework screen in the central hallway separates the entry area from the rear hall. This lace-like screen rests on a panelled wooden base with rod-and-bead molding. The single-flight stairway leading to the second floor is in the rear hall and features a turned newel post and turned balusters. The hallway has plaster walls and ceiling, beaded wood wainscoting, a 2-inch crown mold, and a 9 1/2-inch baseboard.

Doors throughout the house are five-panel topped by single-light transoms, while panelled pocket doors with oval escutcheon plates and finger grasp hardware separate the parlor from the dining room. Windows and doors on the first level have molded trim with bull's-eye cornerblocks, while the moldings of the second level do not have the bull's-eye cornerblocks. The house retains its six original mantelpieces, four of which have mirrored overmantels. Like the hallway, the parlor also has a beaded wood wainscot. Wood panelling was added to some of the rooms in 1965, but with removal could allow the original plaster underneath to be restored. The major rooms retain their original chandeliers.

A garage, accessible from the alley, was added to the west (rear) elevation in 1972. At the southwest corner of the lot, adjacent to the alley, stands the original servants quarters constructed at the same time as the main house. The materials on this building are original with little or no changes since construction. The structure is in poor condition, but serves as an example of the methods of construction employed on the main house.

**8. Statement of Significance**

Certifying official has considered the significance of this property in relation to other properties:

nationally     statewide     locally

Applicable National Register Criteria     A     B     C     D

Criteria Considerations (Exceptions)     A     B     C     D     E     F     G

Areas of Significance (enter categories from instructions)

Architecture  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

Period of Significance

1906  
\_\_\_\_\_  
\_\_\_\_\_

Significant Dates

1906  
\_\_\_\_\_  
\_\_\_\_\_

Cultural Affiliation

N/A  
\_\_\_\_\_  
\_\_\_\_\_

Significant Person

N/A  
\_\_\_\_\_

Architect/Builder

Linder, Ambrose: Builder & Designer  
\_\_\_\_\_

State significance of property, and justify criteria, criteria considerations, and areas and periods of significance noted above.

The DeJean House is architecturally significant within the residential context of Pascagoula, being one of only a few Queen Anne cottages in the city that retain integrity. A boom in the lumber industry from 1888 to 1910 stimulated Pascagoula's growth, and as a result many houses were constructed (see Historic Resources of Pascagoula cover document). A survey of the surviving houses dating to this period indicates that most are relatively modest late Victorian vernacular houses, some of which have stock millwork applied in an attempt to make them fashionable. Houses built in a self-conscious effort to imitate the popular Queen Anne style are relatively few in number, and only a handful of well-preserved examples remain. The DeJean House, built in 1906, is one of only seven Queen Anne cottages remaining in Pascagoula that retain integrity. Two of these--the Bodden House and Colle Company Housing--are simple builders' Queen Anne examples of the gable-front-and-wing form, and both are listed in the National Register. The other four include 4215 Pine Street (c. 1900), which is an element of the Krebsville Historic District and is in only fair condition; the Farragut House (1899), which is in very deteriorated condition; the Swartwout House (1908), a Free Classic example listed in the National Register; and 1101 Beach Boulevard, a c. 1900 house that had Queen Anne elements added in 1908. There are only six surviving two-story Queen Anne houses in the city, of which only three retain integrity.

The DeJean House is a good example of the Queen Anne style, with such details as gables clad in imbricated shingles, a bay window, a wraparound porch with turned columns, corner brackets, turned balusters, and a circular corner pavilion. The floor-length windows opening onto the veranda are a regional building tradition, designed to allow the cool gulf breezes into the house. The interior boasts such fine features as an elaborately detailed spindlework screen in the central hallway, beaded wood wainscoting, panelled pocket doors, five-panel doors topped by transoms and surrounded by molded trim with bulls-eye cornerblocks, original light fixtures, and six original

See continuation sheet

**United States Department of the Interior  
National Park Service**

**National Register of Historic Places  
Continuation Sheet**

DeJean House, Pascagoula, Jackson County, Mississippi

Section number 8 Page 1

---

mantelpieces, four of which have mirrored overmantels. Although the north end of the porch was enclosed around 1912 and asbestos siding was added in 1954 when the lap siding was scorched, the house retains integrity of location, design, setting, workmanship, feeling and association.




At the turn of the century the area along Krebs Avenue, one-half block south of the DeJean House, was a major business district that contributed to the residential areas that developed around it. The original owner of the DeJean House, Valsin Pierre DeJean, owned and operated his family's business on Krebs Avenue. Valsin Pierre DeJean also served as Jackson County's Commissioner of Finance from 1919 to 1940 and 1945 to 1953. His parents came to Scranton (the name of this portion of Pascagoula prior to 1904) in 1884 and established the DeJean and Mitchell General Mercantile and Ship Chandlery, which was one of the original businesses developed along Krebs Avenue. A circa 1896 publication noted that of the ship chandleries, DeJean and Mitchell was the largest business house of Scranton, with stock valued at about \$25,000. The house was built in 1906 by a builder, Ambrose Linder, for Valsin Pierre DeJean and his bride, May Mundy. The house has remained in the DeJean family.

United States Department of the Interior  
National Park Service

# National Register of Historic Places Continuation Sheet

DeJean House, Pascagoula, Jackson County, Mississippi

Section number 7 Page 2



UPPER LEVEL DEJEAN HOUSE (APPROX. 1040 SF)  
1/16" = 1'-0"

LOWER LEVEL - DEJEAN HOUSE (APPROX. 3,000 SF)  
1/16" = 1'-0"

DeJean House  
3603 Frederic Street  
Pascagoula, Jackson County, Mississippi

**United States Department of the Interior  
National Park Service**

**National Register of Historic Places  
Continuation Sheet**

DeJean House, Pascagoula, Jackson County, Mississippi

Section number   9   Page   1  

---

DeJean, Julia-Mae, Daughter of Valsin Pierre DeJean. Interviewed by Cindy Obier, Architect with BRUCE B. TOLAR ARCHITECT, Ocean Springs, at Pascagoula, Mississippi. May 8, 1992 and May 12, 1992.

Tolar, Bruce, Architect, Ocean Springs. Inspection of DeJean House, April 23, 1992 / April 28, 1992 / April 30, 1992 / May 5, 1992.

**9. Major Bibliographical References**

Pascagoula, Jackson County, Historic Resources of Pascagoula, MS, Multiple Resource Nomination. May 1991.

Pascagoula, Jackson County, Multiple Resource Survey For Pascagoula, Jackson County, MS. August 15, 1987.

Mississippi Department of Archives and History, Jackson. Historic Resources Inventory Files. Pascagoula, Jackson County.

DeJean, Julia-Mae, Daughter of Valsin Pierre DeJean. Interviewed by Bruce Tolar, Architect, Ocean Springs, at Pascagoula, Mississippi. April 23, 1992.

See continuation sheet

Previous documentation on file (NPS):

- preliminary determination of individual listing (36 CFR 67) has been requested
- previously listed in the National Register
- previously determined eligible by the National Register
- designated a National Historic Landmark
- recorded by Historic American Buildings Survey # \_\_\_\_\_
- recorded by Historic American Engineering Record # \_\_\_\_\_

Primary location of additional data:

- State historic preservation office
- Other State agency
- Federal agency
- Local government
- University
- Other

Specify repository: \_\_\_\_\_

**10. Geographical Data**

Acreage of property Less than one acre

UTM References

A 16 350035 3360590  
 Zone Easting Northing

C \_\_\_\_\_

B \_\_\_\_\_  
 Zone Easting Northing

D \_\_\_\_\_

See continuation sheet

Verbal Boundary Description

The nominated property occupies the East 181 feet of Lot 3, Block 10 of the Rene Krebs Tract located in Section 5, Township 8 South, Range 6 West.

See continuation sheet

Boundary Justification

The boundary includes that portion of city Lot 3 that has historically been associated with the property.

See continuation sheet

**11. Form Prepared By**

name/title Bruce B. Tolar, Architect

organization BRUCE B. TOLAR ARCHITECT date 9 November 1992

street & number 624 Jackson Avenue telephone (601) 872-2598

city or town Ocean Springs state Mississippi zip code 39564

**United States Department of the Interior  
National Park Service**

**National Register of Historic Places  
Continuation Sheet**

DeJean House, Pascagoula, Jackson County, Mississippi

Section number \_\_\_\_\_ Page 1  
Photographs

---

The following information is the same for all photographs:

- (1) DeJean House
- (2) Pascagoula, Jackson County, Mississippi
- (3) Bruce B. Tolar
- (4) April 1992
- (5) Mississippi Department of Archives and History


- Photo 1 - (6) Front (east) facade, view to west
- Photo 2 - (6) Front (southeast) facade, view to northwest
- Photo 3 - (6) Entrance gate at Frederic Street entrance to site
- Photo 4 - (6) Interior - rear hall at stairs, view to east
- Photo 5 - (6) Interior - entry foyer screen detail, view to west
- Photo 6 - (6) Interior - dining room mantelpiece, view to south
- Photo 7 - (6) Interior - bedroom #1 (upper level) fireplace mantelpiece,  
view to north

United States Department of the Interior  
National Park Service

# National Register of Historic Places Continuation Sheet

DeJean House, Pascagoula, Jackson County, Mississippi

Section number \_\_\_\_\_ Page \_\_\_\_\_





DeJean House  
3603 Frederic Street  
Pascagoula, Jackson County, Mississippi

United States Department of the Interior  
National Park Service

# National Register of Historic Places Continuation Sheet

DeJean House, Pascagoula, Jackson County, Mississippi


Section number \_\_\_\_\_ Page \_\_\_\_\_



DeJean House  
 3603 Frederic Street  
 Pascagoula, Jackson County, Mississippi

DEJEAN HOUSE - 306 FREDERIC ST, PASCAGOULA, JACKSON COUNTY, MS  
U.T.M. REFERENCES:  
16/350035/3360590

PASCAGOULA SOUTH QUADRANGLE  
MISSISSIPPI-JACKSON CO.  
7.5 MINUTE SERIES (TOPOGRAPHIC)







DeJEAN House, Pascagoula, Jackson Co., MS

Photo 2 of 7



DEJEAN House


PHOTO 3 of 7

Pascagoula, Jackson Co., MS



Le JEAN TOUSSE,

Photo # of 7



LE JEAN HOUSE

PHOTO 5 OF 7



DEJEAN House,

Photo 6 of 7

Pascagoula, Jackson Co., MS



DE JEAN HOUSE, Pascagoula, Jackson Co., MS

Photo 7 of 7