

**NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY - NOMINATION FORM**

(Type all entries - complete applicable sections)

STATE: Mississippi	
COUNTY: Adams	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE
APR 11 1972	

1. NAME	
COMMON: Natchez Bluffs and Under-the-Hill Historic District	
AND/OR HISTORIC:	

2. LOCATION			
STREET AND NUMBER:			
CITY OR TOWN: Natchez			
STATE Mississippi	CODE 39120	COUNTY: Adams	CODE 001


3. CLASSIFICATION			
CATEGORY (Check One)	OWNERSHIP	STATUS	ACCESSIBLE TO THE PUBLIC
☒ District ☐ Site ☐ Object ☐ Building ☐ Structure ☐ Object	☐ Public ☐ Private ☒ Both	Public Acquisition: ☐ In Process ☐ Being Considered	☒ Occupied ☐ Unoccupied ☐ Preservation work in progress
PRESENT USE (Check One or More as Appropriate):			
☒ Agricultural ☒ Commercial ☐ Educational ☐ Entertainment	☐ Government ☐ Industrial ☐ Military ☐ Museum	☒ Park ☒ Private Residence ☐ Religious ☐ Scientific	☐ Transportation ☐ Other (Specify) Comments

4. OWNER OF PROPERTY			
OWNER'S NAME: City of Natchez and multiple private			
STREET AND NUMBER: Natchez City Hall, 120 South Pearl Street			
CITY OR TOWN: Natchez	STATE: Mississippi	CODE 39120	CODE 28

5. LOCATION OF LEGAL DESCRIPTION			
COURTHOUSE, REGISTRY OF DEEDS, ETC: Office of the Chancery Clerk, Adams County Courthouse			
STREET AND NUMBER: Market Street			
CITY OR TOWN: Natchez	STATE: Mississippi	CODE 39120	CODE 28

6. REPRESENTATION IN EXISTING SURVEYS			
TITLE OF SURVEY: Natchez Trace Parkway Survey			
DATE OF SURVEY: 1940	☒ Federal ☐ State ☐ County ☐ Local		
DEPOSITORY FOR SURVEY RECORDS: National Park Service, U. S. Department of the Interior			
STREET AND NUMBER: 801 19th Street, N.W.			
CITY OR TOWN: Washington	STATE: District of Columbia	CODE 08	

SEE INSTRUCTIONS



STATE: Mississippi	COUNTY: Adams	ENTRY NUMBER APR 11 1972	FOR NPS USE ONLY DATE
------------------------------	-------------------------	------------------------------------	--------------------------

7. DESCRIPTION

CONDITION	(Check One)					
	☐ Excellent	☐ Good	☐ Fair	☒ Deteriorated	☐ Ruins	☐ Unexposed
	(Check One)			(Check One)		
	☒ Altered	☐ Unaltered	☐ Moved	☒ Original Site		

DESCRIBE THE PRESENT AND ORIGINAL (if known) PHYSICAL APPEARANCE

The boundaries of the Natchez Bluffs and Under-the-Hill Historic District are as follows:

Beginning at the intersection of the southerly line of Franklin Street with the westerly line of Broadway; thence westerly along the projection of the southerly line of Franklin Street to the east bank of the Mississippi River. Thence down the river in a southerly direction to the northerly edge of the right-of-way of U. S. Highways 65 and 84 (at the Natchez-Vidalia Bridge). Thence in a southeasterly direction along the right-of-way of U. S. Highways 65 and 84 to the intersection with the northerly right-of-way of the Natchez and Southern Railroad; thence along said northerly right-of-way in a northeasterly direction to the intersection with the easterly property line of the General Box Company property; thence along the easterly property line of the General Box Company to the southerly line of Green Street; thence along the southerly line of Green Street to the westerly line of Canal Street; thence along the westerly line of Canal Street in a northerly direction to the northerly line of Compress Street; thence along the northerly line of Compress Street in a westerly direction to the westerly right-of-way of the Natchez and Southern Railroad; thence along the westerly right-of-way of the Natchez and Southern Railroad and the westerly line of Broadway to the intersection with the southerly line of Franklin Street, the point of beginning.

The principal features of the district are the Natchez landing (Under-the-Hill) and, above it on the bluffs, the city park/promenade and the site of the second Fort Rosalie built by the French at Natchez.

Begun in 1730, the fort was eventually to have been, according to official reports, a substantial brick complex with platforms, vaulted powder magazine, barracks, and other buildings, but it was presumably completed on a less ambitious scale:

This fort is in the shape of a pentagon, each side of which measures fifty steps, tolerably secured against assault by its situation, being placed at a sufficient elevation to command the surrounding country. Its glacis is of turf and its parapet of thick oaken planks, and the inner fortification and ditch well stockaded. It is provided with some few cannon. Its garrison

SEE INSTRUCTIONS

SEP 20 1971

NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY - NOMINATION FORM

(Continuation Sheet)

STATE	
Mississippi	
COUNTY	
Adams	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE
APR 11 1972	

(Number all entries)

7.

consists ordinarily of fifty men and three officers.
(From "Journal of the Chickasa War," 1739, as re-
printed by J. F. H. Claiborne in Mississippi as a
Province, Territory and State, p. 68.)

When occupied by the British at the close of the Seven Years' War,
Fort Rosalie (renamed Fort Panmure) was thus described in a report
by the inspecting officer:

...to put this Fort in a state of Defence, the
Platforms ought to be entirely New laid, as both
the Timber and planks are so rotten, that they will
not support the weight of the Cannon, the Stockades
and Gates of the Covert way are in the same condi-
tion. When I took possession of it, one of the
principal Gates of the Fort, and one of the Covert
way leading to the water, were entirely unhinged,
and the place not tenable against a party with
small Arms, and the Communication between the
Officers Barracks and the Fort open. (Major Robert
Farmar to the Secretary of State, January 24, 1764,
as reprinted in Mississippi Provincial Archives,
1763-1766; English Dominion, p. 9.)

A 1796 engraving of the fort from the Atlas accompanying General
Victor Callot's Voyage in North America (reproduced by Justin
Winsor in The Mississippi Basin, p. 453) depicts a palisaded
enclosure containing a two-story barracks and five smaller
structures, three of which appear to function as observation
towers.

Fort Rosalie was disestablished by the United States in 1801
following acquisition of the Natchez District, but the site
continued to capture the interest of travelers for years there-
after:

Fort Penmure [sic], on the edge of the bluff is
now in ruins, but the situation, and the extent
of the old ramparts, prove it to have been a post
of considerable consequence. It effectually com-
mands the river, without being commanded itself,
and the view from it is very extensive, particular-
ly over the flat swamps of Louisiana, on the opposite
side of the Mississippi. (P. Cuming, Sketches of a
Tour to the Western Country, p. 295.)

Although by the late nineteenth century, the remains of
Fort Rosalie had largely been effaced, its location was designated
on an 1891 map of Natchez drawn by Charles W. Babbit, city and

NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY - NOMINATION FORM

(Continuation Sheet)

STATE Mississippi	
COUNTY Adams	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE
	APR 11 1972

(Number all entries)

7.
county surveyor. Gerard Brandon, writing in 1899, noted that traces of the fort were still discernible near the cotton compress on the bluff, an observation confirmed by Dunbar Rowland eight years later. During the early 1940s a purported replica of the fort, complete with stockade, barracks, officers' quarters, storehouse, powder magazine, and blacksmith shop, was erected on the site by local entrepreneur Jefferson Davis Dickson, but the two buildings which remain standing today are ruinous and the area overgrown except for a clearing planted in vegetable gardens.

The top of the bluffs from the intersection of Silver Street and Broadway to Franklin Street is maintained by the City of Natchez as a public park and planted in grass, magnolias, oaks, cedars, and pines. The setting is further enhanced by a number of benches, a bandstand which commands a panoramic view of the river, and a fountain mounted on circular concrete tiers, a gift to the city by the local Rotary Club on that organization's fiftieth anniversary in 1969.

In seeking early accounts of the physical appearance of that portion of the historic district which became Natchez-Under-the-Hill, one is tempted to begin with a description by Pierre Lemoyne d'Iberville of what he encountered on the initial voyage of French exploration up the Mississippi River in 1700:

I reached the landing place of the Natchez....From ...the river one ascends a very steep hillside about 150 fathoms high covered completely with woods. Being on top of the hill one finds a country of plains and prairies filled with little hills, in some places groves of trees....(From Iberville's Journal, as reprinted by John R. Swanton in Indian Tribes of the Lower Mississippi Valley and the Adjacent Coast of the Gulf of Mexico, pp. 190-191.)

The details are insufficient for positive identification, however, and in one instance appear to preclude it, for the "hillside about 150 fathoms high" is only about one-sixth the height of that which today overlooks the landing.

One of the few first-hand descriptions of eighteenth-century Under-the-Hill after it had begun to acquire its river-port identity is that by George Willey (1787-1874), who in old age remembered that

...there were but two or three houses on the hill, the whole town being under the hill, which was then quite an extensive tract. Below, where is

NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY - NOMINATION FORM

(Continuation Sheet)

STATE	
Mississippi	
COUNTY	
Adams	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE
APR 11 1972	

(Number all entries)

7.

now the ferry landing, there was quite an extensive and heavy battery, known as "the King's Works," and just above, there was a quarter race track extending from the bluff towards the river. ("Natchez in the Olden Times," reprinted by J. F. H. Claiborne in Mississippi as a Province, Territory and State, p. 527.)

J. F. H. Claiborne noted that at the time of the American Revolution, all of Natchez had still been under the hill, with twenty frame and log houses and four stores built on the batture, or land reclaimed from the exposed river bed. In his description of a visit to Natchez in 1789 (reprinted by Edith Wyatt Moore in Natchez Under-the-Hill, p. 26), Father Antonios Gonzales of Sargossa, Spain, implied that the upper town had begun to emerge but was still secondary to Under-the-Hill. By the turn of the century, however, the balance had so shifted that an English traveler saw the landing in 1807 as only "a few houses immediately under the bluff." Yet on its own scale, and exuding its own flavor, the lower town grew along with the upper:

On looking round me for a moment, on landing, I was far from agreeably impressed with the general appearance of the buildings....The principal street, which terminates at the ascent of the hill, runs parallel with the river, and is lined on either side with a row of old wooden houses.... extending along the Levee to the north, commences the mercantile part of the "landing," lined with stores and extensive warehouses, in which is transacted a very heavy business. (J. H. Ingraham, The South-West by a Yankee, pp. 18-20.)

Although the physical layout of Under-the-Hill throughout its history has been subjected to change as a result of erosion and landslides alternating with buildup of the batture, the main street has always been Silver Street, running southwest from Broadway down the hill to intersect Fulton Street, which extends west to meet the river. Leading north from Fulton Street and lying between Silver Street and the river is Water Street (earlier there was a third artery, Levee Street, nearest the bank and generally parallel to Silver and Water Streets, but it has since been submerged). The southern portion of Under-the-Hill features the continuation of Silver Street and, branching from it near the former ferry dock, Ferry Street. Little Street, running in a plane with upper Silver Street, though farther against the bluff, was projected on early maps but apparently not developed. Short cross streets similar to Fulton Street were once in evidence up and down the landing: Maiden Lane, Porter Street, Earhart's

NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY - NOMINATION FORM

(Continuation Sheet)

STATE	
Mississippi	
COUNTY	
Adams	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE
	APR 11 1972

(Number all entries)

7.
Alley, and Cypress Street.

In addition to the racetrack, private dwellings, saloons, hotels, warehouses, fisheries, and grocery stores which lined the streets of nineteenth-century Under-the-Hill, there was a coalyard, incongruously but handsomely housed in a vaguely Italianate-looking structure on the river bank at Fulton Street, and an icehouse and a municipal waterworks on Water Street. The most distinctive features of the waterfront were the ark-like wharfboat moored at the foot of Fulton Street, its rambling superstructure surmounted on a low-slung hull and serving as a public steamboat landing, and the Bluff City Railroad, which operated on an inclined track between the wharfboat and a number of firms in the upper town.

Although the Natchez landing still supports a few commercial shrimp fishermen and a repair barge which services river tugs on an emergency basis, little remains physically to tell the story of its lusty past. There are six one and two-story rectangular brick buildings of undetermined age and original usage still standing on the east side of Silver Street, some of which are inhabited and all of which are delapidated. The most evocative remnant of the six is the third one to the south, a narrow, three-bay structure with "false front" embellished by a dentiled brick panel above the cornice line and carved wooden lintels over the second floor door and windows. An ornamental iron balustrade around the balcony is identical to that which once adorned the galleries of Windsor, the plantation home of the Daniell family which burned in nearby Claiborne County in 1890. (Parts of the Windsor balustrade, as well as a flight of exterior iron stairs, are installed at the Chapel of Alcorn College, Lorman, Mississippi, and it is not unlikely that a section of the balustrade was also removed to Under-the-Hill.) The almost-Federal style of the fourth building to the south is accented by stepped gables, dentiled brick cornice, soldier coursework over the second-floor fenestration, and decorative anchor irons and grille attic vents. Four shanties, three of them occupied, line the east side of Water Street, which extends approximately five hundred yards north along the river bank. At the opposite end of Under-the-Hill, less than half a dozen neat frame cottages, some with lawns and gardens, comprise the section known as "Little Mexico."

8.
of the more strategically located Fort Adams, thirty-five miles south of Natchez on the boundary between the United States and Spanish West Florida. The lands and buildings of Fort Panmure were sold in 1801 to William Dunbar, planter, scientist, and explorer of the Old Southwest, and ca. 1820 a subsequent owner,

SIGNIFICANCE

PERIOD (Check One or More as Appropriate)

☐ Pre-Columbian

☐ 16th Century

☒ 18th Century

☒ 20th Century

☐ 15th Century

☐ 17th Century

☒ 19th Century

SPECIFIC DATE(S) (If Applicable and Known)

AREAS OF SIGNIFICANCE (Check One or More as Appropriate)

☐ Aboriginal

☐ Education

☒ Political

☒ Urban Planning

☐ Prehistoric

☐ Engineering

☐ Religion/Phi-

☐ Other (Specify)

☒ Historic

☐ Industry

losophy

☒ Agriculture

☐ Invention

☐ Science

☐ Architecture

☐ Landscape

☐ Sculpture

☐ Art

Architecture

☐ Social/Human-

☒ Commerce

☒ Literature

itarian

☐ Communications

☒ Military

☐ Theater

☐ Conservation

☐ Music

☒ Transportation

STATEMENT OF SIGNIFICANCE

The area in and around the Natchez Bluffs and Under-the-Hill Historic District is associated with the earliest recorded history of the Old Southwest. In 1700, Pierre Lemoyne d'Iberville selected the home of the Natchez Indians, where the city of Natchez now stands, as the future site of a fortified settlement. Sixteen years later the first Fort Rosalie was erected by Jean Baptiste Lemoyne Bienville, brother of d'Iberville, and named in honor of the wife of the Count of Ponchartrain, Minister of Marine Affairs. Control of the culturally advanced Natchez tribe, as well as domination of river traffic and communication, had influenced the choice of site, which within a few years became the nucleus of a thriving agricultural community. The success of the latter was largely based on abuses dealt the Indians, however (chief of which was appropriation of their lands), and in retaliation 232 French men, women, and children were massacred on November 28, 1729, and Fort Rosalie subsequently destroyed. The Natchez were in turn dispersed westward across the river by a punitive expedition sent from New Orleans and they never regained their tribal identity. Their tragedy would later be rendered by the French author François Auguste, Vicomte de Chateaubriand (1768-1848), into some of the most avidly read romantic fiction of the early nineteenth century: René, Atala, and Celuta; or the Natchez.

Fort Rosalie was rebuilt during 1730-1734, but with the decline in cultivation of French agricultural holdings in the area, it became a mere way station for river travel. In 1763, following England's triumph over France in the Seven Years' War, it was occupied by British troops and thereafter known as Fort Panmure in honor of a minister of George III. Although with the new name it assumed new significance (that of a frontier outpost on an international boundary), the fort was garrisoned for less than four of the sixteen years in which England held it before yielding to Spanish appropriation during the American Revolution. Pro-British settlers of the Natchez District staged an abortive rebellion in 1781, but Fort Panmure continued in Spanish possession until the American flag was raised over the works on March 30, 1798. It was occupied only briefly by the United States before being abandoned in favor

SEE INSTRUCTIONS

9. MAJOR BIBLIOGRAPHICAL REFERENCES

Alexander, Capt. J. E. Transatlantic Sketches. Philadelphia: Key and Biddle, 1833. P. 249.
 Brandon, Gerard. "Historic Adams County." Publications of the Mississippi Historical Society, II (1899), pp. 206-218.
 Chambers, Moreau Browne Congleton. "The History of Fort Panmure at Natchez, 1763-1779." Master's thesis, Duke University, 1942.
 City of Natchez. A Request for an EDA Technical Assistance Grant for Planning of the Comprehensive Development of the

10. GEOGRAPHICAL DATA

LATITUDE AND LONGITUDE COORDINATES DEFINING A RECTANGLE LOCATING THE PROPERTY			LATITUDE AND LONGITUDE COORDINATES DEFINING THE CENTER POINT OF A PROPERTY OF LESS THAN TEN ACRES		
CORNER	LATITUDE	LONGITUDE	LATITUDE		LONGITUDE
	Degrees Minutes Seconds	Degrees Minutes Seconds	Degrees	Minutes	Seconds
NW	31° 33' 51"	91° 24' 24"			
NE	31° 33' 41"	91° 24' 13"			
SE	31° 33' 13"	91° 24' 48"			
SW	31° 33' 23"	91° 24' 58"			

APPROXIMATE ACREAGE OF NOMINATED PROPERTY: **75 acres**

LIST ALL STATES AND COUNTIES FOR PROPERTIES OVERLAPPING STATE OR COUNTY BOUNDARIES

STATE:	CODE	COUNTY:	CODE

11. FORM PREPARED BY

NAME AND TITLE: Dawn Maddox, Architectural Historian		DATE: August 31, 1971
ORGANIZATION: Mississippi Dept. of Archives and History		
STREET AND NUMBER: Post Office Box 571		
CITY OR TOWN: Jackson	STATE: Mississippi 39205	CODE: 28

12. STATE LIAISON OFFICER CERTIFICATION

NATIONAL REGISTER VERIFICATION

As the designated State Liaison Officer for the National Historic Preservation Act of 1966 (Public Law 89-665), I hereby nominate this property for inclusion in the National Register and certify that it has been evaluated according to the criteria and procedures set forth by the National Park Service. The recommended level of significance of this nomination is:

National ☒ State ☒ Local ☒

Name

R. A. McLemore
R. A. McLemore

Title

Director, Miss. Dept. of Archives and History

Date

August 31, 1971

I hereby certify that this property is included in the National Register.

Robert M. Utley
 Chief, Office of Archeology and Historic Preservation

Date

4/11/72

ATTEST:

St. Bradford
 Keeper of The National Register
February 15, 1972

SEE INSTRUCTIONS

NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY - NOMINATION FORM

(Continuation Sheet)

STATE	
Mississippi	
COUNTY	
Adams	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE
	APR 11 1972

(Number all entries)

8.

Peter Little, erected north of the fort site his mansion Rosalie, now headquarters of the Mississippi Daughters of the American Revolution. The remaining fort acreage is presently in multiple private ownership and partially developed into a residential district.

A lingering local tradition that the 1716-1729 Fort Rosalie physically survived the Natchez uprising to become the Fort Rosalie/Fort Panmure of later years is negated by contemporary communications of the French colonial government. It is more difficult to determine whether or not the two forts shared the same site, however. John Monette, in History of the Mississippi Valley, p. 214, described the 1716-1729 fort as "remote from the bluff which overlooks the river...near the eastern limit of the present [1848] city of Natchez," a statement which is substantiated by J. F. H. Claiborne and Dunbar Rowland. Contemporary references to the location of the first fort are given in relation to the principal village of the Natchez Indians, i.e., the fort is identified as being between the river and the village. The latter was estimated by eyewitnesses such as Jean Penicaut and Dumont de Montigny to be one league to one-and-a-quarter leagues from the river, which corresponds to the modern measurement of three miles between the river and the village site (now the Fatherland Plantation or Grand Village of the Natchez Indians and designated a national historic landmark). As shown on de Montigny's ca. 1725 map of Fort Rosalie and environs (reproduced by Robert S. Neitzel in Archaeology of the Fatherland Site: The Grand Village of the Natchez, plate 1), the fort was midway between river and village, thus indicating a distance of more than a mile from the river to the fort as opposed to the present approximately five hundred yards between the river and the site of the 1730-1734 fort. Shifting of the river's edge and the distortion of perspective in de Montigny's map are factors to be considered, of course, but in the case of the latter, it is clear that de Montigny did not intend to depict the fort on the brow of the bluff, for between it and the river are individual dwellings (Indian and French) with cultivated areas nearby.

In a report to Count Maurepas, Minister of the Navy, in 1731, Perier, Governor of Louisiana, noted that after the massacre of two years before, a fort had been built at Natchez "on the bank of the river," which specification perhaps implies that the earlier fort had not been so situated. At this point in time, the issue will likely be resolved only by archaeological excavation, but there is no doubt that the second fort was built on the bluff within the proposed historic district. Approximately equidistant from the site, and also within the district boundaries are the former locations of two local industries, both now demolished: toward the north, the nineteenth-century Natchez

NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY - NOMINATION FORM

(Continuation Sheet)

STATE	
Mississippi	
COUNTY	
Adams	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE
	APR 11 1972

(Number all entries)

8.

compress, where cotton bales were compacted en route to the loading docks on the wharf below, and on the south, a factory built ca. 1920 which manufactured lumber products (packing boxes, plywood, and veneer) for nearly four decades under a succession of ownerships.

The city park farther north along the bluffs has served as such since the emergence of the upper town, having been created as a public green or common during the administration of Manuel Gayosa de Lemos, Spanish governor of the Natchez District, 1789-1798. Trees were planted, and for a time the granting of lots was forbidden as far inland as Canal Street in order to provide open space for the benefit of the settlement. Although the area which it encompasses has diminished, the park continues to serve the same purpose as when it impressed early visitors to the city:

The front, or first parallel street, is laid out about one hundred yards back from the verge of the bluffs, leaving a noble green esplanade along the front of the city, which not only adds to its beauty, but is highly useful as a promenade and parade ground. Shade trees are planted along the border, near the verge of the precipice, beneath which are placed benches, for the comfort of the lounge. From this place the eye commands one of the most extensive prospects to be found on the Mississippi. To a spectator, standing in the centre of this broad, natural terrace, the symmetrical arrangement of the artificial scenery around him is highly picturesque and pleasing.
(J. H. Ingraham, The South-West by a Yankee, pp. 22-23.)

In 1909 the Mississippi Daughters of the American Revolution dedicated a stone marker in the park to commemorate the terminus of the Natchez Trace, and near it fly the five flags which have been raised over Natchez: French, English, Spanish, Confederate, and American.

The river landing beneath the bluffs was presumably established early in the period of French colonization and served in turn the British, Spanish, and Americans who occupied the fort and populated the growing town. With the beginning of the Mississippi territorial period (1798), the landing became the southwesternmost outlet of the United States and a factor in negotiations for the Louisiana Purchase. Although characterizations of Under-the-Hill which date from the 1700s, like physical descriptions, are rare, its unsavory reputation appears to have originated in the early years of the century which

NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY - NOMINATION FORM

(Continuation Sheet)

STATE	
Mississippi	
COUNTY	
Adams	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE
APR 11 1972	

(Number all entries)

8.

followed. The Mississippi River, supporting flatboat and keelboat traffic, generated the development of a criminal element in Under-the-Hill which was augmented by the proximity of the Natchez Trace, a six-hundred mile trail which threaded the wilderness between Nashville and Natchez. Boatmen, gamblers, river pirates, highwaymen, and prostitutes populated the port, of which one visitor wrote in 1810: "...for the size of it, there is not, perhaps in the world, a more dissipated spot." The coming of steam navigation after 1811 apparently altered the image of Under-the-Hill only for the worse:

Dreadful riots occur then [in the spring of the year], - "fist and scull fighting," where eyes are gouged out, noses and ears bitten and torn off; at that season too the passengers of the steam-boats are plundered in the following manner: - In the evening a steamer stops at Natchez to land or take in goods, the passengers observe several houses lighted up, and hear the sounds of fiddles and merriment, and they run up to see what is going on; they find men and women dancing, gambling, and drinking, the bell of the steam-boat rings to announce that she is about to continue her voyage, the lights in the houses of entertainment are immediately extinguished, and the passengers immediately rush out, afraid of being too late for the boat, and run down towards the landing; ropes are drawn across the road, the passengers fall heels over head, a number of stout ruffians throw themselves upon them, and strip them of their money and watches, and they get on board in doleful plight, and of course never see or hear more of their plunderers. (Capt. J. E. Alexander, Transatlantic Sketches, p. 249.)

Changing conditions, however, in time wrought an accompanying change in the character of Under-the-Hill. The bandit-plagued trace gave way to a well-established stage route, and steamboating increased the volume of river trade to the extent that respectable mercantile firms and hotels found it expedient to share the landing with the barrooms and brothels. Growing security of travel by land and river and the transformation of Under-the-Hill into one of the world's most flourishing cotton markets stimulated a zeal for periodic clean-ups of its less reputable sections. One steamer passing downriver to New Orleans reported that she saw at Natchez

several boats crowded with persons who had been ordered from that place, in consequence of their

NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY - NOMINATION FORM

(Continuation Sheet)

STATE	
Mississippi	
COUNTY	
Adams	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE
APR 11 1972	

(Number all entries)

8.

abandoned character, and also saw, at Ellis' Cliffs, eighteen miles below Natchez, one or two flatboats freighted with the same description of person, but principally females - all bound down the Mississippi. (Reprinted by Virginia Park Matthias in "Natchez-Under-the-Hill," The Journal of Mississippi History, Vol. VII, p. 220.)

One of the severest blows to the image of Under-the-Hill as, in the words of one critic, "the early American Sodom" was dealt not by vigilantes but by the tornado of 1840. Contemporary newspaper accounts indicate the landing was devastated, with 400 lives lost and over one hundred flatboats, two steamboats, a ferry, and numerous buildings destroyed by strong winds and waves ten to fifteen feet high. Although the lower town, like the upper, recovered in time, it thereafter increasingly reflected the interests of legitimate business operations.

At the beginning of the Civil War, fourteen companies of Confederate soldiers debarked from Under-the-Hill, but actual conflict did not reach it until September 2, 1862. On that date a gunboat from the USS Essex landed to procure ice for sick crew members and was fired on by the home guard. In retaliation for the killing of one seaman and the wounding of five others, the Essex shelled the Natchez heights and the landing, but the latter, being more exposed to gun range, suffered greater damage both from the bombardment and the fires which followed. One civilian, a seven-year-old girl, was killed before the town unconditionally surrendered.

Following the war and the passing of the golden era of steamboating, Under-the-Hill went into a gradual economic decline which terminated in its demise upon completion of the Natchez-Vidalia Bridge in 1940 and the simultaneous ceasing of ferry operations across the Mississippi. Yet the reputation and the appeal of the place persist, as demonstrated by the number of visitors to the antebellum mansions of the upper town who year after year find their way down Silver Street as well. A request for a technical assistance grant for development of the area as a major tourist attraction was submitted by the City of Natchez to the Economic Development Administration of the U. S. Department of Commerce in 1967 but was deferred. Local support for the proposal continues, however, and both private and public ownership recognize the need for including in any such undertaking the adjoining acreage on the bluffs in addition to the more obvious asset of the landing itself. The former is essential as a contiguous zone to protect the approaches to and the setting of Under-the-Hill, and it has intrinsic historic

NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY - NOMINATION FORM

(Continuation Sheet)

STATE Mississippi	
COUNTY Adams	
FOR NPS USE ONLY	
ENTRY NUMBER APR 11 1972	DATE

(Number all entries)

8.

associations of its own which merit interpretation: the Fort Rosalie site and the Natchez Trace. The National Park Service of the U. S. Department of the Interior is currently considering the bluffs as a location for the southern terminus of the Natchez Trace Parkway, and the City of Natchez has offered to make its property there available for that purpose.

9.

Mississippi River Bluffs at Natchez, Mississippi, as a Major Tourist Attraction. Natchez: The City of Natchez, Adams County, Mississippi, 1967.

Claiborne, J. F. H. Mississippi, as a Province, Territory and State. Jackson, Miss.: Power & Barksdale, 1880. Pp. 47, 527.

Cuming, F. Sketches of a Tour to the Western Country. Pittsburgh: Cramer, Spear & Eichbaum, 1810. P. 295.

Gandy, Thomas H., M.D. Personal Collections, Natchez, Mississippi.

Ingraham, J. H. The Southwest by a Yankee. New York: Harper & Brothers, 1835. Vol. II, pp. 15-27.

Maddox, Dawn. Personal Inspection, June 26 and 27, 1971.

Matthias, Virginia Park. "Natchez-Under-the-Hill." The Journal of Mississippi History, VII (January, 1945), pp. 201-221.

Mississippi Department of Archives and History, Jackson, Mississippi. Map File: (1) Babbit, Charles W. "Map of the City of Natchez and Suburbs, Adams County, Mississippi, 1891."
(2) Jordan, Kaiser & Sessions. "Map of Portion of Prince Estate Under the Hill, City of Natchez, Adams County, Mississippi, 1956."
(3) Sloan, Theo W. "Map Showing Part of Natchez, Mississippi, Known as Under the Hill, as Shown by Deed Records, 1829."

Photograph File: (1) "Natchez-Under-the-Hill"

Subject File: (1) "Fort Rosalie"

(2) "Natchez-Under-the-Hill"

Monette, John W., M.D. History of the Discovery and Settlement of the Valley of the Mississippi. New York: Harper & Brothers, 1848. Vol. I, pp. 214-215.

Moore, Edith Wyatt. Natchez Under-the-Hill. Natchez: Southern Historical Publications, Inc., 1958.

Neitzel, Robert S. Archeology of the Fatherland Site: The Grand Village of the Natchez. New York: Anthropological Papers of the American Museum of Natural History, 1965. Vol. 51, Part 1, pp. 58-62 and Plates 1 and 2.

NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY - NOMINATION FORM

(Continuation Sheet)

STATE	
Mississippi	
COUNTY	
Adams	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE
	APR 11 1972

(Number all entries)

9.

Phelps, Dawson A., and Jennings, Jesse D. A Preliminary Study of the Natchez Trace Parkway and Historical and Archeological sites in and near Natchez, Mississippi. United States Department of the Interior, National Park Service, Natchez Trace Parkway, 1943. Manuscript Collections (typescript), Mississippi Department of Archives and History, Jackson, Mississippi. Pp. 9-19.

Rowland, Dunbar, ed. Encyclopedia of Mississippi History. Atlanta: Southern Historical Publishing Association, 1907. Vol. I, pp. 736-739

Rowland, Dunbar, ed. Mississippi Provincial Archives, 1763-1766; English Dominion. Nashville, Tenn.: Press of Brandon Printing Company, 1911. Vol. I, p. 9.

Rowland, Dunbar, and Sanders, A. G., eds. Mississippi Provincial Archives, 1729-1740; French Dominion. Jackson, Mississippi: Press of the Mississippi Department of Archives and History, 1927. Vol. I, p. 70

Shields, G. B., comp. Code of Ordinance of the City of Natchez. Natchez Printing & Stationery Co., 1905. Pp. 181, 183-184, 190-193, 196, 211, 213, 239-240, 244-253, 301-302.

Swanton, John R. Indian Tribes of the Lower Mississippi Valley and Adjacent Coast of the Gulf of Mexico. Smithsonian Institution, Bureau of American Ethnology, Bulletin 43. Washington: Government Printing Office, 1911. Pp. 45-48, 190-191, 205, 336.

Winsor, Justin. The Mississippi Basin. Boston and New York: Houghton, Mifflin and Company, 1898. Pp. 451 and 453.

Natchez Bluffs and Under-the-Hill Historic District

N

SOUTHERN BELL TEL. & TEL. CO.
SUBMARINE CABLE CROSSING

City of Natchez
Natchez City Hall
1964; revised 1969
Scale: 1" = 660 feet

P P

W.H. BRADEN
ELEM. SCHOOL

MARGARET MARTIN
JR. HIGH SCHOOL

[illegible][illegible]

Natchez Bluffs and Under-the-Hill Historic District

City of Natchez
Natchez City Hall
1964; revised 1969
Scale: 1" = 660 feet

SOUTHERN BELL TEL. & TEL. CO.
SUBMARINE CABLE CROSSING

Streets shown include: BEECH ST, IRVING ST, POGO ST, OCTOBER ST, JOA ST, OSCAR ST, SOUTH ST, PERCY ST, JOINER ST, HAWTHORN ST, MARIN ST, ROGERS ST, SIMMONS ST, GREEN ST, ROSALE ST, SOUTH ST, WILBURN ST, ETRICHMAN ST, WALL ST, AVE, BROADWAY, BONTURA ST, PARKER ST, BANK ST, MARKET ST, BRACKEN ST, COYTON ST, FRANKLIN ST, JEFFERSON ST, LEARNED ST, WASHINGTON ST, WENSEL ST, FOLEY ST, ORLEANS ST, COMMERCE ST, UNION ST, JENKIN ST, RAY ST, PAVENNA ST, HARRISON ST, SOUTH ST, JENKIN ST, RAY ST, W.H. BRADEN ELEM. SCHOOL, MARGARET MARTIN JR. HIGH SCHOOL.

BM 66

31° 35'

POINT

U.S.G.S. 7.5'
Natchez Quadrangle
1963
Scale: 1:24000

91° 25'



MISSISSIPPI RIVER

31° 33' 51"

91° 24' 24"

91° 23' 13"

91° 22' 02"

91° 20' 51"

91° 19' 40"

91° 18' 29"

91° 17' 18"

91° 16' 07"

91° 14' 56"

91° 13' 45"

91° 12' 34"

91° 11' 23"

91° 10' 12"

91° 09' 01"

91° 07' 50"

91° 06' 39"

91° 05' 28"

91° 04' 17"

91° 03' 06"

91° 01' 55"

91° 00' 44"

91° 00' 33"

91° 00' 22"

Natchez-Vidalia Bridge

Bagging Station

Radio Tower

Substation

Providence Ch

Harding Bayou

Braden Sch

Martin Jr High Sch

Routh Cem

WT

BM 218

200

220

240

260

280

300

320

340

360

380

400

420

440

460

480

500

520

540

560

580

600

620

640

660

680

700

720

740

760

780

800

820

840

860

880

900

920

940

960

980

1000

1020

1040

1060

1080

1100

1120

1140

1160

1180

1200

1220

1240

1260

1280

1300

1320

1340

1360

1380

1400

1420

1440

1460

1480

1500

1520

1540

1560

1580

1600

1620

1640

1660

1680

1700

1720

1740

1760

1780

1800

1820

1840

1860

1880

1900

1920

1940

1960

1980

2000

2020

2040

2060

2080

2100

2120

2140

2160

2180

2200

2220

2240

2260

2280

2300

2320

2340

2360

2380

2400

2420

2440

2460

2480

2500

2520

2540

2560

2580

2600

2620

2640

2660

2680

2700

2720

2740

2760

2780

2800

2820

2840

2860

2880

2900

2920

2940

2960

2980

3000

3020

3040

3060

3080

3100

3120

3140

3160

3180

3200

3220

3240

3260

3280

3300

3320

3340

3360

3380

3400

3420

3440

3460

3480

3500

3520

3540

3560

3580

3600

3620

3640

3660

3680

3700

3720

3740

3760

3780

3800

3820

3840

3860

3880

3900

3920

3940

3960

3980

4000

4020

4040

4060

4080

4100

4120

4140

4160

4180

4200

4220

4240

4260

4280

4300

4320

4340

4360

4380

4400

4420

4440

4460

4480

4500

4520

4540

4560

4580

4600

4620

4640

4660

4680

4700

4720

4740

4760

4780

4800

4820

4840

4860

4880

4900

4920

4940

4960

4980

5000

5020

5040

5060

5080

5100

5120

5140

5160

5180

5200

5220

5240

5260

5280

5300

5320

5340

5360

5380

5400

5420

5440

5460

5480

5500

5520

5540

5560

5580

5600

5620

5640

5660

5680

5700

5720

5740


5760

5780

5800

5820

5840





UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE

NATIONAL REGISTER OF HISTORIC PLACES
PROPERTY PHOTOGRAPH FORM

(Type all entries - attach to or enclose with photograph)

STATE	
Mississippi	
COUNTY	
Adams	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE
APR 11 1972	

1. NAME

COMMON: Natchez Bluffs and Under-the-Hill Historic District

AND/OR HISTORIC:

2. LOCATION

STREET AND NUMBER:

CITY OR TOWN:

Natchez

STATE:

Mississippi 39120

CODE

28

COUNTY:

Adams

CODE

001

3. PHOTO REFERENCE

PHOTO CREDIT: Mississippi Department of Archives and History

DATE OF PHOTO: June 1971

NEGATIVE FILED AT: P.O. Box 571, Jackson, Mississippi 39205

4. IDENTIFICATION

DESCRIBE VIEW, DIRECTION, ETC.

Site of second Fort Rosalie (1730-1734) built by the French at Natchez, looking north.

SEE INSTRUCTIONS



UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE


NATIONAL REGISTER OF HISTORIC PLACES
PROPERTY PHOTOGRAPH FORM

(Type all entries - attach to or enclose with photograph)

STATE Mississippi	
COUNTY	
Adams	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE
APR 11 1972	

SEE INSTRUCTIONS

1. NAME			
COMMON: Natchez Bluffs and Under-the-Hill Historic District			
AND/OR HISTORIC:			
2. LOCATION			
STREET AND NUMBER:			
CITY OR TOWN:			
Natchez			
STATE:	CODE	COUNTY:	CODE
Mississippi 39120	28	Adams	001
3. PHOTO REFERENCE			
PHOTO CREDIT: Howard B. Peabody			
DATE OF PHOTO: February, 1971			
NEGATIVE FILED AT: Post Office Box 1700 Natchez, Mississippi 39120			
4. IDENTIFICATION			
DESCRIBE VIEW, DIRECTION, ETC.			
Facade and south elevation of third building on east side of Silver Street, proceeding northeast.			





UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE


NATIONAL REGISTER OF HISTORIC PLACES
PROPERTY PHOTOGRAPH FORM

(Type all entries - attach to or enclose with photograph)

STATE Mississippi	
COUNTY Adams	
FOR NPS USE ONLY	
ENTRY NUMBER APR 11 1972	DATE

SEE INSTRUCTIONS

1. NAME			
COMMON: Natchez Bluffs and Under-the-Hill Historic District			
AND/OR HISTORIC:			
2. LOCATION			
STREET AND NUMBER:			
CITY OR TOWN: Natchez			
STATE: Mississippi 39120	CODE 28	COUNTY: Adams	CODE 001
3. PHOTO REFERENCE			
PHOTO CREDIT: Howard B. Peabody			
DATE OF PHOTO: February, 1971			
NEGATIVE FILED AT: P.O. Box 1700 Natchez, Mississippi 39120			
4. IDENTIFICATION			
DESCRIBE VIEW, DIRECTION, ETC. Facade (west elevation) of third building on east side of Silver Street, proceeding southwest.			



1



1 Silver Street

Natchez Bluffs and Under-the-Hill District

Natchez, Adams Co., Mississippi

Looking southeast, the western facade and northern elevation before rehabilitation when only the new roof had been installed.



UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE

NATIONAL REGISTER OF HISTORIC PLACES
PROPERTY PHOTOGRAPH FORM

(Type all entries - attach to or enclose with photograph)

STATE	
Mississippi	
COUNTY	
Adams	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE
APR 11 1972	

SEE INSTRUCTIONS

1. NAME			
COMMON: Natchez Bluffs and Under-the-Hill Historic District			
AND/OR HISTORIC:			
2. LOCATION			
STREET AND NUMBER:			
CITY OR TOWN:			
Natchez			
STATE:	CODE	COUNTY:	CODE
Mississippi	39120	Adams	001
3. PHOTO REFERENCE			
PHOTO CREDIT: Dr. Thomas H. Gandy			
DATE OF PHOTO: August, 1971			
NEGATIVE FILED AT: Mississippi Department of Archives and History			
P. O. Box 571, Jackson, Mississippi 39205			
4. IDENTIFICATION			
DESCRIBE VIEW, DIRECTION, ETC.			
City Park, Natchez Bluffs, looking north: Rotary Club Fiftieth Anniversary Fountain.			





UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE

NATIONAL REGISTER OF HISTORIC PLACES

PROPERTY PHOTOGRAPH FORM

(Type all entries - attach to or enclose with photograph)

STATE Mississippi	
COUNTY Adams	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE
	APR 11 1972

SEE INSTRUCTIONS

1. NAME			
COMMON: Natchez Bluffs and Under-the-Hill Historic District			
AND/OR HISTORIC:			
2. LOCATION			
STREET AND NUMBER:			
CITY OR TOWN: Natchez			
STATE: Mississippi 39120	CODE 28	COUNTY: Adams	CODE 001
3. PHOTO REFERENCE			
PHOTO CREDIT: Howard B. Peabody			
DATE OF PHOTO: February, 1971			
NEGATIVE FILED AT: Post Office Box 1700 Natchez, Mississippi 39120			
4. IDENTIFICATION			
DESCRIBE VIEW, DIRECTION, ETC. Silver Street, looking southwest.			





NATCHEZ BLUFFS AND UNDER-THE-HILL HISTORIC DISTRICT, NATCHEZ, MISS

NATCHEZ-UNDER-THE-HILL FROM THE FOOT OF SILVER STREET, LOOKING NORTHEAST.
CA. 1880.

FROM THE COLLECTION OF DR. THOMAS H. GANDY
408 N. PEARL STREET
NATCHEZ, MISS. 39120

NOT TO BE REPRODUCED WITHOUT PERMISSION OF DR. GANDY

NPS Number April 11, 1972 (6)
Title: Natchez Bluffs and Under-
the-Hill Historic District
Loc. Adams City, Miss.
Natchez-Under-the-Hill
from the foot of Silver Street,
looking Northeast.